


Kincardine Bridge Southern Piled Viaduct Replacement



Excellence
Collaboration
Innovation
Integrity

Our Company



Formed in 2000 by market leading highway maintenance, design and construction organisations.














Collaboration





Integrity

Our Contracts






Perth Inverness Edinburgh Killin Lochgelly Fort William Oban Ardelve Dundee Chryston Kintore Dunbeath Ballinluig Inveraray Kingussie Stirlinghill Keith Queensferry Bonnyrigg Charlesfield Rosyth Burghmuir

Contract Arrangements





BEAR Scotland and Balfour Beatty are contracted separately by **Transport** Scotland.

BEAR manage the project on behalf of TS.

Balfour Beatty is principal contractor and will construct the works.





- Kincardine Bridge South approach opened 1936
- Comprises 24-span piled viaduct, 76.2m in length followed by nine 15.2m concrete spans and seven 30.5m steel spans.
- This project will demolish the 76.2m Southern Piled Viaduct (SPV)
- Replace with new five-span structure of similar appearance to the adjacent existing structure
- Temporary bridge constructed to west of existing structure
- Traffic diverted onto the temporary structure to minimise disruption during demolition and construction



Why This Work Is Necessary





- Approach piled viaduct in poor condition
- Assessed as substandard
- Temporary propping since 1992,
- Originally planned for five years, itself is now in need of major refurbishment.
- If left weight restrictions and lane closures will need to be applied
- Ultimately a full bridge closure



Kincardine Bridge SPV Replacement

Public Meeting





Site Team

Project Manager Craig Hunter

Site Agent Craig Drennan

Social Impact Manager Duncan Gardner

Ecological Clerk of Works Stewart Parsons




Project Overview

Existing Structure	Cat A Listed bridge opened in 1936. Southern Piled Viaduct Spans 1 to 5 have been temporarily propped since the 90s and this is now life expired.
Replacement Structure	5-Span (80m) Reinforced Concrete bridge replicating the adjacent existing spans. Existing Parapets and Lighting Columns removed, restored and reerected.
Temporary Structure	Balfour Beatty designed temporary bridge maintaining vehicular and pedestrian passage across Kincardine Bridge.
Temporary Working Platform	Balfour Beatty designed, to be removed entirely upon completion.



Site Access











































Traffic Management

Works have been planned to minimise disruption to road users. Traffic management will only be implemented where required to ensure the safety of the public and site workers.

May 15 th for 3 weeks	A876 Southbound across Clackmannanshire Bridge, off-peak slow lane closure with a 30mph speed limit
October 2023	Night-time lane closures across Kincardine Bridge. Temporary signals in operation
November 2023	Weekend closure of Kincardine Bridge
	West Footpath – pedestrian and cyclist access maintained throughout

On completion of the new bridge, the Traffic Management will be the same but carried out in the reverse order.



Ecology

- Environmental Impact Assessment and Habitats Regulations Assessment completed as part of planning stage which outlines the key environmental and ecological mitigation which is required for the project. This includes
 - Appointment of Qualified and Experienced Ecological Clerk of Works (ECoW) who will visit site to ensure mitigation measures are implemented and effective and provide any advice/ecological surveys needed as part of the works.
 - Additional ECoW appointed to act on behalf of Transport Scotland to review working methods and complete bird surveys on the salt marsh during the works.
 - Water management plan in place to ensure all dewatering activities and site runoff is treated before being discharged from site.
 - 2m high fencing will be erected from September to March inclusive to provide screening between the works and the overwintering birds.
 - Saltmarsh management plan prepared to ensure the affected saltmarsh is fully restored upon completion of works. We have appointed the Centre for Ecology and Hydrology to do these works and monitoring due to their expertise in this area.



Duncan Gardner – Social Impact Manager

Balfour Beatty Regional Scotland: 2022 Social Impact Report





Some of our planned benefits for the project

- Job opportunities
- Work placements
- School engagement for careers and STEM
- Support for local community garden, growing and refilling station, food bank and forest school
- Guided ecology walks
- Donation of litter picking equipment and volunteer days
- And more!

Thank You

